


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 10 Twp. 21 Rge. (E) 13 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW NE SE  
Lease Owner Westgate-Greenland Oil Company, et al  
Lease Name Rothgarn Well No. 3  
Office Address 1022 Union National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hol  
Date well completed March 13, 1950 19  
Application for plugging filed March 13, 1950 19  
Application for plugging approved March 13, 1950 19  
Plugging commenced March 13, 1950 19  
Plugging completed March 13, 1950 19  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	250	8 5/8	250	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3635 to 250 feet,  
Drove wooden plug and run 20 sacks cement and  
Filled hole with heavy mud to 15 feet and set plug,  
Run 5 sacks cement to cellar base.

3-21-50

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company  
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler  
1022 Union National Bank Building, Wichita 2, K (Address)

SUBSCRIBED AND SWORN to before me this 20th day of March, 1950  
Esther Russell Notary Public.

My commission expires May 25, 1953



COMPANY: Mallard Drilling Company  
Westgate-Greenland Oil Co.

CONTRACTOR: Mallard Drilling Company

FARM: Rothgarn #3 Sec. 10-21-13  
Mc Pherson County, Kansas

LOCATION:

COMMENCED: March 4, 1950

COMPLETED: March 12, 1950

0	to	80	Sand
80	to	249	Iron, sand and shale
249	to	870	Red shale
870	to	1500	Shale and shells
1500	to	1720	Lime
1720	to	1900	Lime
1900	to	2075	Lime
2075	to	2185	Lime
2185	to	2315	Lime and shale
2315	to	2485	Lime and shale
2485	to	2645	Lime and shale
2645	to	2785	Lime and shale
2785	to	2900	Lime
2900	to	2980	Lime
2980	to	3050	Lime
3050	to	3135	Lime
3135	to	3215	Lime
3215	to	3285	Lime and shale
3285	to	3370	Lime
3370	to	3458	Lime
3458	to	3518	K.C. Lime
3518	to	3543	Red and gray shale
3543	to	3633	Conglomerate
		3633	T.D. Rotary

Set 250 feet of 8 5/8" surface pipe. Cemented with 165 sacks cement.

TOPS: K.C. Lime 3458      Brown Lime 3274  
No ar buckle

Measurements taken from derrick floor

DRY, ABANDONED AND PLUGGED

MAR 8 1950

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Rothgarn #3, Section 10-21-13, Mc Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

**PLUGGING**  
FILE SEC-10-T-21-R-130  
BOOK PAGE 142 LINE 43

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County Kansas, this 20th day of March 1950.

*Marshall Wright*

My commission expires 12/4/52