

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,594-0000

LEASE NAME Denker

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 22S RGE. 12 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Vantage Petroleum, Inc.

ADDRESS P. O. Box 553, Great Bend, Kansas 67530

PHONE# (316) -792-3664 OPERATORS LICENSE NO. 04973

Date Well Completed 7/5/89

Character of Well D&A

Plugging Commenced 7/5/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/5/89

The plugging proposal was approved on 7-5-89 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3770'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	322'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mud laden fluid 3770'-3671' 10 sks cement @ 40'
50 sks cement @ 3671' 15 sks cement in rathole
50 sks cement @ 680' 15 sks cement in wtr. well
50 sks cement @ 360'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Kyle B. Branum


P.O. Box 506, Russell, KS 67665-0506

7-6-89

SUBSCRIBED AND SWORN TO before me this 5th day of July, 19 89

STATE CORPORATION COMMISSION

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public



Commission Expires: 2-6-92
CONSERVATION DIVISION
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. BOX 506
 RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Vantage Petroleum, Inc.
 P. O. Box 553
 Great Bend, Kansas 67530

CONTRACTOR: Emphasis Oil Operations
 Box 506
 Russell, KS 67665

LEASE: Denker

WELL #1

LOCATION: SE SE SE
 Section 9-22S-12W
 Stafford County, Kansas

LOGGERS TOTAL DEPTH: 3769'

ROTARY TOTAL DEPTH: 3770'

COMMENCED: 6/28/89

CASING: 8-5/8" @ 322' w/215 sks cement

ELEVATION: 1869' K.B.

COMPLETED: 7/5/89

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Clay	165'	Toronto	3172'
Shale	653'	Lansing-KC & Base KC	3307'-3538'
Anhydrite	677'	Viola	3560'
Red Bed	1200'	Simpson	3611'
Shale & Lime Stks.	2859'	Arbuckle	3671'
Top of Topeka	2860'	R.T.D.	3770'
Heebner	3154'		

RECEIVED
 STATE CORPORATION COMMISSION

JUL - 6 1989

CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Kyle B. Branum
 Kyle B. Branum

Subscribed and sworn to before me on July 5, 1989.

My commission expires: February 6, 1992.



Glenda R. Tiffin
 Glenda R. Tiffin, Notary Public