

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 9 Twp. 22 Rge. 12 (E) (W)

Location as "NE/CNW%SW%" or footage from lines E/2 SE/4

Lease Owner Empire Drilling Company

Lease Name Denker Well No. 2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 12/30/66 19

Plugging completed 1/2/67 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Elving

Producing formation Depth to top Bottom Total Depth of Well 3673 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	338	none
				5 1/2	3670	2595

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked hole to 3630', sanded back to 3600' and ran 5 sacks of cement. Cleaned cellar. Rigged up on 5 1/2" casing, broke and removed cellar slips, worked pipe to 22" tension at 20 points. Shot pipe at 2647' and 2585', worked pipe loose. Pulled 35 joints 5 1/2" casing. Finished pulling 5 1/2" casing, cleared floor, loaded rack, lowered mast, racked unit. Talled pipe.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

1-19-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RTCE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 16 day of Jan, 1967

My commission expires Oct 22-1970

Notary Public.

Veeder Supply &amp; Dev'l. Co.



Cherryvale, Kansas

Drilled for Joe Davis & Harry Gore Farm Denker No. #2 Depth 3673'  
 Contractor Veeder Supply & Development Company Pipe 3670' of 5 1/2" Csg. Cemented same.  
 Location E/2 SE/4 Sec. 9 Twp. 22 Range 12  
 Commenced 11-29-49 Completed 12-14-49 County Stafford State Kansas

Sand Shale	0	180	180
Red Bed	180	338	158
Red Bed Rock	338	635	297
Shale	635	1110	475
Shale Shells	1110	1410	300
Anhydrite Shale	1410	1510	100
Broken Lime	1510	1630	120
Lime Shale	1630	2275	645
Sand	2275	2290	15
Lime Shale Breaks	2290	2310	20
Lime Shale	2310	2400	90
Shale Shells	2400	2500	100
Shale Lime Shells	2500	2765	265
Shale	2765	2775	10
Lime Shale	2775	2825	50
Shale Shells	2825	2840	15
Sand	2840	2860	20
Shale	2860	2895	35
Lime	2895	2985	90
Lime Shale	2985	3100	115
Lime	3100	3155	55
Lime Shale	3155	3250	95
Shale	3250	3310	60
K.C. Lime	3310	3365	55
Lime Shale	3365	3410	45
Lime	3410	3445	35
Lime Cherty	3445	3472	27
Lime	3472	3605	133
Lime Chert	3605	3615	10
Shales Sand	3615	3640	25
Shale	3640	3671	31
Arbuckle Lime	3671	3673	2
Total Depth			3673'

## Tops:

Lansing - 3306  
 Viola - 3560  
 Simpson - 3609  
 Arbuckle - 3667

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 12 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS  
 MONTGOMERY COUNTY SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says;  
 I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know  
 and on oath state, that the above drilling log covering the Denker #2 Well  
 in Section 9-22-12, Stafford County, Kansas, is true and correct.  
 Further affiant saith not.

THE VEEDER SUPPLY &amp; DEVELOPMENT COMPANY

By Floyd W. Hild  
 Floyd W. Hild

Subscribed and sworn to before me this 15<sup>th</sup> day of December, 1949.

Lester Lanson  
 Notary Public

My Commission Expires: 7-11-52