


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec 9 Twp. 22 Rge. 12 (E) (W)
Location as "NE/CNW&SW&" or footage from lines W/2 SE SE
Lease Owner: Empire Drilling Company
Lease Name: Denker Well No. 1
Office Address: Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed: 19
Application for plugging filed: 19
Application for plugging approved: 19
Plugging commenced: 12/22/66 19
Plugging completed: 1/2/67 19
Reason for abandonment of well or producing formation: depleted.

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Elving
Producing formation: Depth to top: Bottom: Total Depth of Well: 3671 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	338	none
				5 1/2	3669	2429

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked hole to 3670', pushed plug to 3300', ran 50 gallons sand to 3250' and 5 sacks of cement. Cleaned cellar, loaded hole with our water truck, couldn't get ring out of braden head. Had Tom's Welding Service out to cut ring out of head, rigged up on 5 1/2" casing, had 23" stretch, shot pipe at 2846', 2728', 2611'. Mud came in pipe, could not get shot down, took pressure pump and water truck, pumped mud out of pipe, shot pipe at 2502' and 2420', pipe came loose, pulled 15 joints. Pulled 9 joints, broke weld on flange on drive line, tore shaft off. Took it in. Put shaft back in, pulled 28 joints 5 1/2" casing. Finished pulling 5 1/2" casing, lowered mast, racked unit, tallied pipe. Took extension off, loaded unit and rack. Pumped 80 sacks cement and 10 sacks mud.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PULLING COMPANY
Address: CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 16 day of Jan, 1967

My commission expires Oct 22 - 1970 Notary Public.

Harry Gore
Denker # 1

Sec. 9. Twp. 22, Rge. 12
Stafford County, Kansas

Total Depth: 3671'
Comm: 8/30/49
Comp: 9/14/49

Top: Lansing 3304'
Top: Arbuckle 3668'

Casing

Cement

8 5/8" Set @ 338'
5 1/2" Set @ 3669'

200 Sacks
150 Sacks

Formation:

Depth:

Surface Clay	15
Sand	80
Coarse Sand	125
Shale	150
Sand Shale	215
Red Shale & Sand	275
Red Shale	460
Red Bed & Shell	650
Anhydrite	683
Shale & Shell	1150
Salt, Shale	1510
Lime	1580
Anhydrite & Shale	1685
Lime	1735
Shale, Lime	1770
Lime & Shale	1840
Shale	1860
Lime & Shale	1985
Lime & Shale	2055
Shale	2190
Lime & Shale	2340
Shale Lime, Shells	2480
Lime & Shale	2680
Shale Shells	2740
Lime & Shale	2970
Lime	2990
Shale	3070
Lime	3248
Shale	3296
Lime	3525
Lime & Shale	3550
Conglomerate	3560
Lime	3590
Comm & Lime	3637
Shale & Lime	3670
T.D.	3671

RECEIVED
STATE CORRUPTION COMMISSION
DEC 12 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SE
RUSSELL, COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Violet Keller
.....

Subscribed and sworn to before me this 20th day of December 1949

[Signature]
.....
Notary Public

My commission expires: 6/17/50