


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 9 Twp. 22 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines E/2 SW/4 SE/4
Lease Owner Empire Drilling Company
Lease Name Denker Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/19/66 19
Plugging completed 1/2/67 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation Depth to top Bottom Total Depth of Well 3686 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	340	none
				5 1/2	3685	2607

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked hole to 3686', sanded to 3675' and ran 5 sacks of cement. Cleaned cellar, rigged up on 5 1/2" casing, broke and removed cellar slips, worked pipe to 23" tension, shot pipe at 3043', no change in tension. Shot pipe at 2816', 2700', 2595', worked pipe loose, pulled 40 joints of 5 1/2" casing, took radiator off unit, had fixed. Finished pulled 5 1/2" casing, 83 joints total, cleared floor, loaded rack, lowered mast, racked unit. Tallied pipe, moved out.
Pumped 80 sacks cement and 10 sacks mud.

RECEIVED
STATE CORPORATION COMMISSION
1-19-67

PLUGGING COMPLETE.

JAN 19 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 14 day of Jan, 1967
Notary Public.

My commission expires Oct 22-1970

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Joe Davis & Harry Gore Farm Denker No. #3 Depth 3685'
 Contractor Veeder Supply & Development Company Pipe 34.0' of 8-5/8" Csg. Cemented with 175 sacks.
 Location E/2 SW/4 SE/4 Sec. 9 Twp. 22 Range 12
 Commenced 12-5-49 Completed 12-29-49 County Stafford State Kansas

Surface Soil Sand	0	180	180
Red Bed	180	340	160
Red Bed	340	550	210
Shale	550	1125	575
Shale Lime Shells	1125	1415	290
Anhydrite Shale	1415	1540	125
Shale Lime	1540	1770	230
Lime	1770	1835	65
Shale Lime	1835	1960	125
Lime Shale Breaks	1960	2025	65
Shale Lime Shells	2025	2200	175
Shale Shells	2200	2375	175
Shale Lime Shells	2375	2640	265
Shale Lime	2640	2885	245
Lime	2885	2980	95
Lime Shale	2980	3095	115
Lime	3095	3240	145
Lime Shale	3240	3300	60
Shale	3300	3310	10
K.C. Lime	3310	3540	230
Shale	3540	3565	25
Lime	3565	3570	5
Lime Cherty	3570	3620	50
Shale	3620	3680	60
Lime	3680	3685	5
Total Depth	3685'		

Tops:

Lansing	-	3307
Viola	-	3562
Simpson	-	3614
Arbuckle	-	3677

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 12 1949
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS
 MONTGOMERY COUNTY SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says;
 I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know
 and on oath state, that the above drilling log covering the Denker #3 Well
 in Section 9-22-12, Stafford County, Kansas, is true and correct.
 Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

BY Floyd W. Hild

Subscribed and sworn to before me this 31st day of December 1949.

Charles Lawson
 Notary Public

My Commission Expires: 7-11-52.