


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 9 Twp. 22S Rge. 12W (~~E~~) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Bergman DRILLING, Inc.
Lease Name J. Denker Well No. 1
Office Address 425 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 21 1960
Application for plugging filed January 21 1960
Application for plugging approved January 21, 1960
Plugging commenced January 21, 1960
Plugging completed January 21, 1960
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

285' Surface Pipe - 8-5/8" - Circ.
Filled hole with mud to 240'. Set plug with hulls, displaced 20 sacks cement through drill pipe. Filled hole with mud to 35'. Set plug with hulls. Capped to base of cellar with 10 sacks cement.

RECEIVED
JAN 28 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bergman Drilling, Inc.
Address 425 Union Center, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Harold Bergman (employee of owner) (owner ~~Harold Bergman~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman
Harold Bergman
Bergman Drilling, Inc. 425 Union Center
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January 1960

My commission expires June 30, 1960
Loecile L. Lawson Notary Public.



DRILLER'S LOG

#1 J. Denker, SW NE SE, Sec. 9-22s-12w, Stafford County, Kansas

Date Started: January 11, 1960.

Date Completed: January 21, 1960

* * * * *

0- 40 Surface Clay
 30- 223 Surface Clay
 223- 280 Surface Clay
 280-925 Shale
 925-1125 Shale & Shell
 1125-1140 Shale & Shell
 1140-1460 Shale
 1460-1685 Shale & Lime
 1685-1820 Shale, Shells & Broken Lime
 1820-1985 Shale & Lime
 1985-2120 Shale & Shells
 2120-2320 Lime & Shale
 2320-2435 Lime & Shale
 2435-2635 Shale & Shells
 2635-2785 Shale & Lime
 2785-2835 Shale - Lime
 2835-2980 Shale & Lime
 2980-3070 Shale & Lime
 3070-3128 Lime & Shale
 3128-3175 Shale & Lime
 3175-3310 Lime
 3310-3365 Shale & Lime
 3365-3402 Lime
 3402-3454 Lime
 3454-3475 Lime
 3475-3552 Lime
 3552-3620 Lime Chirt
 3620-3647 Chirt Shale
 3647-3690 Shale
 3690-3710 Arbuckle-
 3710 Total Depth

Elevation 1870' R. B.

GEOLOGICAL TOPS:

Heebner	3172 (-1302)
Toronto	3193 (-1323)
Douglas	3205 (-1335)
Brown Lime	3308 (-1438)
Lansing	3326 (-1456)
Conglomerate	3580 (-1710)
Viola Chert	3584 (-1714)
Simpson Shale	3636 (-1766)
Arbuckle	3691 (-1821)
R. T. D.	3710 (-1840)

RECEIVED
 STATE CONSERVATION COMMISSION
 JAN 23 1960
 CONSERVATION DIVISION
 Wichita, Kansas

* * * * *

A F F I D A V I T

County of Sedgwick)
) SS
 State of Kansas)

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

Harold Bergman

 Harold Bergman

Subscribed and sworn to before me this 27th day of January, 1960.

My Commission expires: June 30, 1963.

Bevile L. Lawson

 Notary Public