

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

STAFFORD County. Sec. (9) Twp. 22 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE

Lease Owner LINDAS OIL COMPANY

Lease Name AHNERT Well No. ONE

Office Address WICHITA KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed 19

Application for plugging filed 19

Application for plugging approved Yes 19

Plugging commenced MAY 19 1952 19

Plugging completed MAY 26 1952 19

Reason for abandonment of well or producing formation:

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

M.A. RIVES

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3674 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	220'	Cemented
				5 1/2"	3675'	2754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole, from 3663' to 3375', with chat,  
Dumped 5 sacks of cement, at 3375', with dump bailor.  
Shot off and pulled 2754', of 5 1/2" pipe.  
Mudded hole to 220', set 15' rock bridge at 220'.  
Dumped 15 sacks of cement, at 205', with dump bailor.  
Mudded hole to 35', set 10' rock bridge at 35'.  
Dumped 10 sacks of cement at 25', to fill and cap top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to John Lindas Oil, Inc.  
Address 1316 Union National Bank Building; Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.

I, F. M. Callaway (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. M. Callaway Treasurer  
1316 Union National Bank Bldg; Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of May, 1952.

My commission expires October 8, 1955

22-5133-s 9-48-10M

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

JUN 6 - 1952  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 9 T 22 R 12  
BOOK PAGE 19 LINE 7

