


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Div.
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 27 Twp. 22S Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner R. W. Rine Drilling Company, etal
Lease Name McComas Well No. 1
Office Address 320 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-22 19 54
Application for plugging filed 11-22 19 54
Application for plugging approved 11-22 19 54
Plugging commenced 11-22 19 54
Plugging completed 11-22 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4095 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| | | 0 | 397' | 8-5/8" | 397' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 4095' to 361 1/2' Heavy rotary mud.
From 361 1/2' to 360' Wooden plug
From 360' to 299 1/2' 20 sx. cement - 1/3 sk. hulls
From 299 1/2' to 35 1/2' Heavy rotary mud
From 35 1/2' to 34' Wooden plug
From 34' to 3' 10 sx. cement - 1/3 sk. hulls
From 3' to surface to cellar.

11-30-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. H. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. R. W. RINE DRILLING COMPANY

(Signature) By J. H. Wilson
320 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 54

My commission expires July 31, 1957

Luddy Kiefer
Notary Public.

PLUGGING
FILE SEC 27 T 22 R 15W
BOOK PAGE 80 LINE 8

DRILLER'S LOG

Company: R. W. Rine

SE-SE-SE

Sec. 27, Twn. 22S Rge. 15W

Farm: McComas Well No: 1

Total Depth: 4095

County: Pawnee, Kansas

Comm: 11/11/54 Comp: 11/22/54

Contractor: Peel Brothers, Inc.

Elevation:

Casing:

8 5/8" A 397' Cem.

Production:

Figures below indicate bottom of formation

| | | |
|------------------------------|----|------|
| Sand | 0' | 130' |
| Sand and shale | | 155 |
| Shale | | 397 |
| Sand Streaks | | 840 |
| Red bed | | 940 |
| Anhydrite | | 975 |
| Shale | | 1275 |
| Shale and shells | | 1525 |
| Shale and sandy streaks | | 1860 |
| Lime and shale | | 1925 |
| Lime | | 2210 |
| Shale and lime | | 2765 |
| Broken lime and shale | | 2960 |
| Shale and lime | | 3430 |
| Lime, shale and sand streaks | | 3530 |
| Shale and lime | | 3590 |
| Lime | | 3945 |
| Shale and lime | | 4010 |
| Lime, shale and sand | | 4065 |
| Lime and shale | | 4095 |
| Total Depth | | 4095 |

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY

Stoddard E. Peel

SUBSCRIBED AND SWORN to before me this 26 day of November

My commission expires September 28, 1957

Norma L. Reese
Notary Public

PLUGGING
SEC 27 T22 R15W
BOOK PAGE 80 LINE 8