


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County. Sec. 27 Twp. 22 Rge. 15 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner Great Bend Pipe & Supply  
Lease Name Sutton Well No. 3  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8/7/67 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8/10/67 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4139 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	234'	none
				5-1/2"	3984'	3003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4139', ran sand to 3950' and ran 5 sacks of cement. Loaded hole with water, shot pipe at 2980', worked pipe loose and pulled pipe. Pumped 25 sacks of mud and 80 sacks of cement. Capped hole and tallied pipe.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 14 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 67

My commission expires February 15, 1971

Margaret Melaker  
Notary Public.

PL

## DRILLERS LOG

COMPANY: Natural Gas and Oil Corporation  
and Cities Service Oil Company

CONTRACTOR: Drilling Department of  
Natural Gas and Oil Corporation

FARM: Sutton No. 3, SW NW NW Sec. 27-22S-15W  
Pawnee County, Kansas

COMMENCED: June 30, 1953 - Rotary  
July 16, 1953 - Cardwell

COMPLETED: July 14, 1953 - Rotary  
July 18, 1953 - Cardwell

ELEVATION: 1995 DF

0	to	135	Sand
135	to	350	Shale
350	to	400	Shale and shells
400	to	490	Sand
490	to	522	Shale and shells
522	to	635	Shale and red bed
635	to	945	Shale and shells
945	to	975	Anhydrite
975	to	1250	Shale and shells
1250	to	1430	Shale and salt
1430	to	1735	Shale and shells
1735	to	1788	Lime and shale
1788	to	2285	Lime
2285	to	3280	Lime and shale
3280	to	3392	Lime
3392	to	3465	Lime and shale
3465	to	3515	Lime
3515	to	3537	Lime and shale
3537	to	3770	Lime
3770	to	3865	Lime and shale
3865	to	3913	Lime and chert
3913	to	3953	Shale and sand
3953	to	3955	Lime
3955	to	3973	Lime and shale
3973	to	3985	Lime
		3985	T. D. RB

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

Set 234 feet of 8 5/8" 34# surface pipe. Cemented with 200 sacks cement and 3 sacks calcium chloride

Set 3984 feet of 5 1/2" casing. Cemented with 150 sacks cement.

TOPS:	Anhydrite	943	Lansing	3535	Viola	3887
	Heebner	3400	Base KC	3766	Simpson	3911
	Brn Lime	3525	Conglomerate	3791	Arbuckle	3971
			Cherty Cong	3868		

## DRILL STEM TESTS:

- #1 3537-45, open 1/2 hr, weak blow 4 min, rec 4' oil specked mud, 210# BHP.
- #2 3743-68, open 1/2 hr, rec. 4' mud, 0 BHP, (Wk Blow 7 min.)
- #3 3909-58, open 1/2 hr, weak blow 9 min, rec. 12' mud, shut in 15 min, 0 BHP.
- #4 3949-68, open 1/2 hr, rec. 15' mud, 0 BHP.
- #5 3973-81, open 1 hr, rec. 2320' free gassy oil, 3060' gas, 690# BHP. IFP 155#, FFP 460#.

Hole bridged and did not get Schlumberger completed. Lane-Wells log run, Perforated 72 holes 3974 1/2 to 82 1/2, filled up 1000' in 1 1/2 hours, swabbed 23 BOPH 750' off bottom, no water. 500 GA swabbed 29 BOPH 2900' off bottom for 7 hours. Putting on pump.

7/18/53 Filed 25 BOPD Temporary Productivity Affidavit. *with*

2359 BOPD 157

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sutton #3, SW NW NW of Section 27-228-15W, Pawnee County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.

Harold A. Burt  
Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas this 21st day of July, 1953.

Esther Unsell  
Esther Unsell, Notary Public

My commission expires May 25, 1957.