

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford

County, Sec. 8 Twp. 22 Rge. 13 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner El Dorado Refining Co.

Lease Name Schmidt Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-25-54 19

Application for plugging filed 8-25-54 19

Application for plugging approved 8-25-54 19

Plugging commenced 8-25-54 19

Plugging completed 8-25-54 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 3827 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 300'.
Set plug @ 300' w/ 1/2 sack hulls & 20 sacks cement through Drill Pipe.
Filled hole to 35' with heavy rotary mud.
Set plug @ 35' w/ 1/3 sack hulls & ten sacks cement to bottom of celler.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker Drig., Inc.
Address 2008 Lakin, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, SS. S. C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley C. Lingreen
2008 Lakin, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August 1954

Notary Public.
STATE CORPORATION COMMISSION

My commission expires 6-25-55

24-7366-S 3-53-20M

PLUGGING
FILE SEC 8-22-13W
BOOK 840540 LINE 14

AUG 31 1954 8-31-54
CONSERVATION DIVISION
Wichita, Kansas

HONAKER DRIG., INC.
2008 LAKIN
GREAT BEND, KANSAS

DRILLERS LOG

Company: The El Dorado Refining Co.
Contractor: Honaker Drig., Inc.
Farm: Schmidt #1
SEC: 8-22-13W
LOC: NE NW NE
Stafford County, Kansas

Total Depth: 3827'
Comm: 8-14-54
Comp: 8-25-54
Casing: 8-5/8" 300'
Elevation: 11907 D.F.

0	40	Top Soil & Sand	
40	270	Sand & Gravel	
270	775	Red Rock & Shale	8-5/8" casing cemented @
775	805	Anhydrite	300' w/ 250 sacks cement
805	850	Shale	& 5 sacks calcium chloride
850	1250	Shale & Shells	
1250	1335	Salt	
1335	1600	Shale & Shells	
1600	1940	Lime & Shale	
1940	1975	Lime	
1975	3220	Lime & Shale	
3220	3334	Lime	
3334	3410	Lime & Shale	
3410	3725	Lime	
3725	3767	Lime & Chert	
3767	3807	Lime	
3807	3827	Lime & Shale	
3827		Total Rotary Depth	D. & A. Plugged Hole.

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

Joe J. Honaker

Subscribed and sworn to before me this 31 day of August 1954.

Joseph J. Fisher
Notary Public

My Commission Expires 6-25-55

RECEIVED
STATE CORPORATION COMMISSION
SEP - 2 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FRI SEC 8 7 22 13W
PAGE 60 LINE 14