

5-185-20655-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 27 Twp. 23 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
SW NW SW

Lease Owner Petroleum Management, Inc.
Lease Name Allen #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed 19 _____
Application for plugging filed 19 _____
Application for plugging approved 19 _____
Plugging commenced 1/20/78 19 _____
Plugging completed 1/25/78 19 _____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3839'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	280	none
				5 1/2"	3838	2725'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed wood plug to 3720' and sanded to 3700', ran 5 sacks cement. Shot pipe
at 2917', 2812', 2720', pulled 84 joints. Halliburton pumped 3 sacks bulls, 20 sacks
gel. Released plug and pumped 100 sacks 50-50 pos with 2% gel and 3% cc.

PLUGGING COMPLETE.

2-6-78

RECEIVED
STATE CORPORATION COMMISSION

FEB 06 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of Jan., 19 78

Margaret Melchner
Notary Public.

My commission expires _____



Drillers Log

15-185-20655-0000

No. 1 Allen

CASING RECORD:

8 5/8" @285' w/280 sx
2% Gel, 3% CC + 100sx
Common

5 1/2" @3838' w/150 sx
Salt St. Poz

TOTAL DEPTH: 3839'

COMPANY: Petroleum Management, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: May 14, 1976

COMPLETED: May 22, 1976

DESCRIPTION:

C/SW 1/4 NW 1/4 SW 1/4
Sec. 27-T23S-R12W
Stafford County,
Kansas

ELEVATION: 1858' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	60	
Sand & Redbed	60	295	
Sand & Shale	295	1000	
Shale	1000	1615	
Shale & Lime	1615	1860	
Shale & Lime	1860	1985	
Lime	1985	2165	
Lime	2165	2200	
Lime	2200	2255	
Lime	2255	2445	
Lime & Shale	2445	2675	
Lime	2675	2870	
Lime	2870	3090	
Lime	3090	3305	
Lime	3305	3440	
Lime	3440	3545	
Lime	3545	3590	
Lime	3590	3592	
Lime	3590	3670	
Lime	3670	3785	
Lime	3785	3836	
Arbuckle	3836	3839	
RTD		3839	

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1977
CONSERVATION DIVISION
Wichita, Kansas


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jean Stocks
Jean Stocks

Subscribed & sworn to before me this 24th day of May, 1976.

D'Ann Drennan
Notary Public



Mailed to CC 5/24/76