

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Co.

Complete Address 217 N. Water Wichita, Ks

Lease Name Frank Hitz Well No. 2

Location 0 W/2 SE/NW Sec. 2 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3571

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 4:00 PM Day 7 Month 1 Year 1972

The above well was plugged as follows:

237 ft 8 5/8 surface pipe cemented with 175 sacks. 3566 ft 5 1/2 long
string cemented with 75 sacks. Top perf. 3235 ft. Push plug to
3200 ft, 5 sacks cement with bailer. Pulled 1995 ft 5 1/2. Set 10 ft
rock bridge at 225 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4984-12