

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
renewal issued October 30, 1967.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1967
11-3-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Clay Newell

Complete Address: Stafford, Kansas 67578

Lease Name Krug Well No. # 1

Location NE NW SW Sec. 2 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3586'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas 67526 License No. 396

Operation Completed: Hour 2:00PM Day 1st Month November Year 1967

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 175 sacks. 3585' of 4 1/2" long string, cemented with 75 sacks. Plug back T.D. 3550'. Top perforation 3291'. Bottom of the hole was sanded to 3250', and cemented with 4 sacks, with cement from 3250' to 3200'. Pipe parted and 234' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 200', bridge plug and rock bridge from 200' to 190'. 5 sacks of cement was mixed in a barrel, and put on plug at 190', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the plug, with cement from 190' to 115'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 11/3/67

INV. NO. 6614-4