

Form CP-3
Rev. 6-26-62



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bea Drilling Company Inc.

Complete Address: Box 247, Ellinwood, Kansas

Lease Name Teichmann Well No. # 2

Location SE NW NE Sec. 2 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3642'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Bea Drilling Company, Inc.

Address: Box 247, Ellinwood, Kansas License No. _____

Operation Completed: Hour 6:00 AM Day 29th Month April Year 1965

The Above well was plugged as follows:

271' of 8 5/8" surface pipe, cement circulated with 165 sacks. Fluid
level in the hole was at 180'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 240', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the ~~above well~~ **INVOICED** was plugged as herein stated.

DATE 4/30/65
INV. NO. 1077-W

Signed: Archie Elving
Well Plugging Supervisor