

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 211 North Broadway  
 Wichita, Kansas

FILE NO. 2-23  
 LOCATION NW-SW-NE  
 SEC. 10 TWP. 22 RGE. 12W

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease ghuert

Operator Stansford Oil & Gas Co. Address Box 7, Ellinwood, Kans

Field \_\_\_\_\_ County Stafford

Total Depth 3665 Feet.

Plugging Contractor Rd. A. Pipe Pulling Co.

Plugging Contractor's License No. 1.

Address Ellinwood, Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 645' cwc 5 1/2" @ 3661' w/ 150 cc/cm.  
 top perf 3329' banded hole to 3315' dumped  
 5 cc/cm. Filled hole with water, shot  
 and pulled 5 1/2" casing. Filled hole with  
 heavy mud to 240' set rock bridge, dumped 20 cc/cm.  
 mud to 35' rock bridge and 10 cc/cm.  
 to base of cellar.

10-11-55

Warren W. Horner  
 District Conservation Agent

Date Oct 6, 1955

WED  
 COMMISSION

OCT 11 1955

CONSERVATION DIVISION  
 Wichita, Kansas

