

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 39-12

LOCATION QW^{1/4}-SW-SF

SEC. 10 TWP. 22 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease K. Teichman - "A"

Operator Stanolind Oil & Gas Co. Address Box #7 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3690 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 646 ft. Circulated with cement
6" casing set at 3680 ft. Cemented with 100 sacks cement
Plugged back to 3640 ft with chat - Blended 5 sacks of
cement at 3640 ft. Shot off & Pulled the 6" casing
Filled hole with mud to 250 ft. Set Rock Bridges &
15 sacks of cement at 250 ft. - Mud to 30 ft. Plug
x 10 sacks of cement at the surface.

Pipe Pulling, Inc. Plugging - Contractors

RECEIVED
STATE CORPORATION COMMISSION 11-6-50

NOV 6 - 1950

CONSERVATION DIVISION
District Conservation Agent R. M. Stough
Wichita, Kansas

Date 11-2-50

PLUGGING
PAGE SEC. 10 TWP. 22 R. 11-W
BOOK PAGE 39 LINE 12