

KANSAS

*AL* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
7-14-72

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co.

Complete Address 217 N Water Wichita, Ks

Lease Name J. Denker Well No. 2

Location SE/NW/SW Sec. 10 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3657

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 11 Month 7 Year 1972

The above well was plugged as follows:

644 ft 8 5/8 surface pipe cemented with 400 sacks. 3655 ft 5 1/2 long  
string cemented with 150 sacks. Top perf. 3324 ft. Set cast iron  
plug at 3250 ft. with 2 sacks cement. Pulled 2200 ft 5 1/2. Set 10 ft  
rock bridge at 260 ft. Fill hole with 4 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed *J. Russell Bihuster*  
Well Plugging Supervisor

INVOICED

DATE 7/14/72  
INV. NO. 6030-W