

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 6 1967

CONSERVATION DIVISION  
Wichita, Kansas

1-6-67

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Spangenberg Well No. # 2

Location C N/2 SE NW Sec. 10 Twp. 22 Rge. 12 (E)    (W) W

County Stafford Total Depth 3665'

Abandoned Oil Well X Gas Well    Input Well    SWD Well    D & A   

Other well as hereafter indicated:   

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 11:15AM Day 2nd Month Jan. Year 1967

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cemented with 150 sacks. 3662' of 5 1/2" long string, cemented with 110 sacks. This is an open hole. Bottom of the hole was sanded to 3650', and cemented with 5 sacks, through the dump bailer. 2800' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 215', bridge plug and rock bridge from 215' to 205'. 5 sacks of cement was mixed in a barrel, and put on plug at 205', through the dump bailer and let set over week-end. Hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 1/6/67

INV. NO. 4569-4