

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1967
1-9-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Spangenberg Well No. # 6

Location CWL SE NW Sec. 10 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3663'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 9:30AM Day 5th Month Jan. Year 1967

The Above well was plugged as follows:

219' of 8 5/8" surface pipe, cemented with 150 sacks. 3363' of 5 1/2" long string, cemented with 110 sacks. Top perferation 3226'. Bottom of the hole was sanded to 3200', and cemented with 5 sacks, through the dump bailer.

2600' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 210', bridge plug and rock bridge from 210' to 200'. 5 sacks of cement was mixed in a barrel, and put on plug at 200', through the dump bailer and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

1/10/67

INV. NO.

4574-22

Signed:

Audie Elving
Well Plugging Supervisor