

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Intent to Drill,  
filed August 30, 1967Operator's Full Name Circle Oil Company, Inc.Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202Lease Name Voigt "B" Well No. # 1Location SE SE SW Sec. 11 Twp. 22 Rge. 12 (E) (W) WCounty Stafford Total Depth 3707'Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sage Drilling Company, Inc.Address: 500 Bitting Bldg., Wichita, Kansas 67202 License No. \_\_\_\_\_Operation Completed: Hour 8:15 AM Day 13th Month Sept. Year 1967

The Above well was plugged as follows:

221' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level  
in the hole was at 80'. 1st cementing plug and 1/4 sack of hulls was pushed in  
fluid to 200', and cemented with 25 sacks, through the drill pipe, with cement  
from 200' to 125'. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',  
and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat  
hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

STATE CORPORATION COMMISSION

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

SEP 15 1967

DATE 9/15/67CONSERVATION DIVISION  
Wichita, KansasINV. NO. 6334-W