

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name Charles Voight "A" Well No. # 1

Location E/2 NW SW Sec. 11 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3633'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:00AM Day 10th Month Feb. Year 1966

The Above well was plugged as follows:

239' of 8 5/8" surface pipe, cemented with 150 sacks. 3628' of 6" long  
string, cemented with 100 sacks. Plug back to 3600'. Top perferation 3312'.  
Bottom plug was pushed to 3300', 50' of sand, and cemented with 5 sacks,  
through the dump bailer. 2400' of 6" long string was recovered from the hole.  
Fluid was up in the hole. Bridge plug was pushed in fluid to 239', rock bridge  
from 239' to 230'. 5 sacks of cement was mixed in barrel, and put on plug at  
230', through the dump bailer, and let set over-night. Next morning hole was  
bailed dry, and hole was filled with 3 1/2 yards of ready-mix cement from 215'  
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/15/66  
INV. NO. 2930-W