

MY
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed February 12, 1968.

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name Leonard Voigt "C" Well No. # 1

Location SE SW SE Sec. 11 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3683'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Ks. 67202 License No.

Operation Completed: Hour 2:15AM Day 15th Month February Year 1968

The Above well was plugged as follows:

214' of 8 5/8" surface pipe, cement circulated. Hole was filled with drilling mud to 200', 1st cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 200', and cemented with 24 sacks, with cement from 190' to 115'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 2/16/68
INV. NO. 7276-W