

KANSAS

X STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sitrin Petroleum Corp.

Complete Address Box 693 Great Bend, Ks

Lease Name Alexander Well No. 2

Location SE/SW/NW Sec. 11 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3650

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:00 PM Day 4 Month 12 Year 1970

The above well was plugged as follows:

223 ft of 8 5/8 surface pipe cemented with 225 sacks. 3627 ft of
5 1/2 long string cemented with 100 sacks. Open hole Sand back to
3600 ft, 5 sacks cement with bailer. Pulled 2600 ft of 5 1/2. Pumped
3 sacks hulls, 15 sacks gel. & 100 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. Russell Baker*
Well Plugging Supervisor

INVOICED

DATE 12/7/70

INV. NO. 3011-W