

Handwritten mark

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 138-19

LOCATION sw-sw-nw

SEC. 11 TWP. 22 RGE. 18-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Oberhaus

Operator Petroleum, Inc. Address 100 Moeby Bldg. Wichita-Kans

Field _____ County Stafford

Total Depth 3663 Feet.

(Describe briefly the manner in which the well was plugged)

Suecoe Pipe 8 1/2" - 195 ft. Circulated with cement.
5 1/2 casing set at 3633 ft. & cemented 100 sacks cement.
Plugged back to 3510 ft. with cement - sand to 3470 ft.
Run in 5 sacks of cement at 3470 ft. Shut off & pulled the
5 1/2 casing - Pumped in 50 sacks of cement - then Plug &
43 sacks of cement - filling hole from 250 ft. to the
surface with cement.

The West Supply Co. - Plugging Contractor

PLUGGING
FILE SEC. 11 T. 22 R. 18-w
BOOK PAGE 138 LINE 19

FEB 5 X 1952 2-5-52
CONSERVATION DIVISION
Wichita, Kansas
C. H. Stovall
District Conservation Agent
Date 2-3-52