



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-185-38349-0000

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

March 12, 1968.

Dear Sir:

Mr. Albert (Buck) Unruh of Southwest Caseing Puling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Building Wichita, Kansas.

Lease Name: Bliss Well No. #2

Location: N/2-NW-SW Sec. 2 Twp. 23 Rge. 13W(E)(W) W

County: Stafford Total Depth 3840' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

275' of 8 5/8" surface pipe circulated with 225 sacks
cement. 3836' of 4 1/2" long string. Sand to 3800' & 4 sacks cement
3120' of 4 1/2" pipe pulled. Pumped 15 sacks mud. Cementing plug
and 90 sacks cement. 3 sacks mud & 10 sacks cement to surface.

Very truly yours,

Herman Guston
 Conservation Division Agent