



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 20 1965

8-20-65  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name: Mason Well No. # 1

Location: NW SW NE Sec. 7 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3722' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

332' of 8 5/8" surface pipe, cement circulated with 315 sacks.  
Fill hole with drilling mud to 325', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*