



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-185-01356-0008

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 16 1963

9-16-63

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name: Kelly-Williams Well No. # 1

Location: NW NW SE Sec. 7 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3942 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Watson was instructed to plug the well as follows:

202' of 8 5/8" surface pipe, cemented with 200 sacks.

3750' of 5 1/2" long string, cemented with 150 sacks. Top

perferation 3605'. Sand to 3590', cement with 5 sacks.

Fill hole with mud to 200', 10' rock bridge, cement with

20 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent