



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

May 14, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Recd.
5-1-82

Dear Sir:

Mr. Rich Wheeler of Woodman-Lannitti Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Green Wolf Oil Company

Complete Address: City National Tower, Suite 1850, Oklahoma City, Oklahoma

Lease Name: McCandless Well No. 1

Location: C 5/2 SE NW Sec. 2 Twp. 22 Rge. 12 (E) (W)

County: Stafford Total Depth: 3588'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Wheeler was instructed to plug the well as follows:

Anhydrite 610' Elev. 1829 KB Circulate hole and Fill with mud.
Pump 50 sacks cement through drill pipe at 450', Pump 30
Sacks cement through drill pipe 260'. Fill hole with mud to 40'
Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
Cement. Cement rat hole with 10 sacks cement. Cement mouse hole
with 10 sacks cement.

Very truly yours,

Conservation Division Agent