

State of Kansas



15-185-20521-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Williamson of Duke Drlg Co has this
date requested permission to plug the following described well:Mr. Williamson guarantees payment of the plugging fee.Operator's full Name: National Developement CoComplete Address: 1300 Union Natl Bldg, Wichita, KSLease Name: Ahnert Well No. 2Location: 1320 FNL & 1020 FEL Sec. 10 Twp. 22S Rge. 12 (E)(W) WCounty: Stafford Total Depth 3665 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Williamson was instructed to plug the well as follows:

255 ft 8 5/8 surface cemented with 225 sacks. Pump plug,
40 sacks cement to 500 ft. 2nd plug at 225 ft, 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Allied Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent