

State of Kansas



15-185-20056-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed August 30, 1967.

Dear Sir:

Mr. Clarence Michaels of Sage Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Compant, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Voigt "B" Well No. # 1

Location: SE SE SW Sec. 11 Twp. 22 Rge. 12 (E)(W) W

County Stafford Total Depth 3707' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

221' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill  
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge, and cement rat hole with 2 sacks.

SEP 15 1967

Very truly yours,

CONSERVATION DIVISION  
Wichita, Kansas

Archie Elving  
Conservation Division Agent