


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 8 Twp. 22 Rge. 14 (E) (W) x

Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Petroleum, Inc.
Lease Name Unruh Well No. #1
Office Address Route #2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8-4-64 19
Plugging completed 8-10-64 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 3915' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						2822.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded off bottom to 3580', mixed and ran 5 sacks cement with dump bailer.
Mixed and pumped 10 sacks gel and 10 sacks weight mud to surface pipe.
Squeezed hole with 10 sacks gel and 75 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1964

CONSERVATION DIVISION
Wichita, Kansas

8-12-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer - Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of August, 1964

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.

DRILLER'S LOG UNRUH NO. 1

Petroleum, Inc., Operator
 Garvey Drilling Company, Contractor

Section 8, Twp. 22S, Rge. 14 W
 Location: SW NE SE
 County: Stafford County, Kansas
 R.T.D.: 3915'
 Production: Arbuckle

Drilling Commenced: January 19, 1953
 Drilling Completed: January 31, 1953
 Casing Record: 8 5/8" @ 223' w/175 sax
 5 1/2" @ 3914' w/100 sax

Figures below indicate bottom of formation:

40 Surface oil
 212 Sand & Shale
 223 Shale
 295 Shale & Shells
 893 Red Bed
 905 Anhydrite
 1275 Shale & Shells
 1450 Salt & Shells
 1650 Shale & Shells
 1960 Lime & Shale
 2200 Lime
 2350 Lime & Shale
 2450 Lime
 2460 Shale
 2595 Lime & Shale
 2980 Shale & Shells
 3433 Lime & Shale
 3757 Lime
 3769 Shale
 3811 Cherty Viola
 3865 Sand
 3915 Lime
 3915 R.T.D.

Tops:

Heebner: 3340 (-1388)
 Brown Lime: 3462 (-1510)
 Lansing: 3472 (-1520)
 Arbuckle: 3865 (-1913)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 25 1964

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W.W. Fisher

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public in said County and State, this 3rd day of February, 1953.

Charlotte Heidner
 Notary Public

My commission expires: October 13, 1954.