


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 8 Twp. 22 Rge. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Herman Geo. Kaiser, et al
Lease Name Fertig Well No. 1
Office Address 909 Palace Bldg. Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-13-59 19
Application for plugging filed 2-13-59 19
Application for plugging approved 2-13-59 19
Plugging commenced 2-14-59 19
Plugging completed 2-14-59 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3894 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257' w/175 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 240 feet w/20 sacks cement; filled hole with rotary mud to 35 feet; set second plug and cemented with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1959

CONSERVATION DIVISION
WICHITA, KANSAS

2-27-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply & Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas COUNTY OF Montgomery ss.
Leo C. Veeder (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder


Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 59

Leo Hanson

Notary Public.

My commission expires July 11, 1960



Veeder Supply & Dev'l. Co.

Cherryvale, Kansas

Drilled for Herman Geo. Kaiser and Francis Oil & Gas, Inc. Farm Fertig No. 1 Depth 389 1/4
 Contractor Veeder Supply and Development Co. Pipe 257' 8 5/8" csg. w/175 sacks
 Location NE/4 NE/4 SW/4 Sec. 8 Twp. 22 Range 14W
 Commenced 1-29-59 Completed 2-14-59 County Stafford State Kansas

Sand	0	195	195	TOPS:	
Shale	195	300	105	Heebner	3350
Shale and sand	300	500	200	Toronto	3370
Shale	500	885	385	Douglas	3388
Shale sand	885	1050	165	Brown Lime	3472
Shale	1050	1660	610	Lansing	3482
Shale and shells, lime	1660	1750	90	Arbuckle	3888
Lime and shale	1750	1785	35		
Lime, shale streaks	1785	1935	150		
Lime	1935	1952	17		
Lime and shale	1952	2175	223		
Lime	2175	2213	38		
Lime and shale	2213	2430	217		
Shale w/lime strks	2430	2508	78		
Lime and shale	2508	2635	127		
Shale w/lime strks	2635	2830	195		
Lime and shale	2830	2975	145		
Shale	2975	3010	35		
Shale w/lime	3010	3110	100		
Shale lime	3110	3175	65		
Lime w/shale strks	3175	3236	61		
Lime and shale	3236	3260	24		
Shale lime	3260	3283	23		
Lime	3283	3705	422		
Lime and shale	3705	3735	30		
Shale lime	3735	3772	37		
Chert lime	3772	3843	71		
Chert, lime, shale	3843	3870	27		
Shale and lime	3870	3882	12		
Lime	3882	3894	12		
T. D.	3894				

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 27 1959
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Fertig #1 well located in Section 8-22-14, Stafford County, Kansas; and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Leo C. Veeder
 Leo C. Veeder

Subscribed and sworn to before me this 17th day of February, 1959.

Leo Lawson
 Notary Public

My commission expires July 11, 1960.

PLUGGING
 FILE SEC 8 T. 22 R. 14W
 BOOK PAGE 19 LINE 6