

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 8 Twp. 22 Rge. 14 (B) (W)
 Location as "NE/CNW/SW" or footage from lines NE SE NW
 Lease Owner Petroleum, Inc.
 Lease Name Standish Well No. 1
 Office Address 305 East Third, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed January 18, 19 53
 Application for plugging filed January 18, 19 53
 Application for plugging approved January 18, 19 53
 Plugging commenced January 18, 19 53
 Plugging completed January 18, 19 53
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
 Producing formation Depth to top Bottom Total Depth of Well 3917 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 210' and set wooden plug at
 210'. Cemented and displaced 20 sacks
 cement through drill pipe onto plug at 210'.
 Mudded up to 35' and set second wooden plug.
 Filled hole to bottom of well cedar with 10
 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
 Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 W. W. Fisher (employee of owner) of the above-described
 well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
 above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. W. Fisher*
 305 East Third, Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 53

My commission expires October 13, 1954

Charlotte [Signature]
 Notary Public.

24-2675-5 2-52-20M
PLUGGING
 FILE SEC 8 T 22 R 14 W
 BOOK PAGE 74 LINE 22

STATE CORPORATION
 JAN 24 1953
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S LOG STANDISH #1

Petroleum, Inc., Operator

Section 8, Twp. 22 S, Rge. 14W

Garvey Drilling Company, Contractor

Location: NE SE NW

Drilling Commenced: January 8, 1953

County: Stafford County, Kansas

Drilling Completed: January 18, 1953

R.T.D.: 3917'

Casing Record: 8 5/8" @ 220' w/175 sax

Production: D & A

Figures below indicate bottom of formation:

45	Surface soil
200	Sand & Shale
220	Shale
300	Shale & Sand
890	Red Bed
920	Anhydrite
1290	Shale & Shells
1440	Salt & Shells
1660	Shale & Shells
2030	Lime & Shale
2130	Lime
2900	Lime & Shale
2970	Shale
3095	Lime
3229	Lime & Shale
3295	Lime
3448	Lime & Shale
3714	Lime
3747	Shale & Lime
3780	Lime
3846	Viola Chert
3865	Shale & Lime
3880	Sand & Shale
3917	Shale

Tops:

Heebner:	3343 (-1490)
Brown Lime:	3463 (-1510)
Lansing:	3474 (-1521)
Viola:	3779 (-1826)
Simpson:	3845 (-1892)

DST #1, 3770-3846, open 40 mins., rec. 15' mud, 0# BHP.

3917' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PLUGGING
 FILE REC 8722R 144
 BOOK PAGE 74 LINE 22

PETROLEUM, INC.

RECEIVED
 JAN 24 1953

By W W Fisher

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 21st day of January, 1953.

Charlotte Heinen
 Notary Public

My commission expires: October 13, 1954.