

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-21415-0000

LEASE NAME WILLIAMS

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #4

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 22 RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 9/16/81

Plugging Commenced 4/13/95

Plugging Completed 4/13/95

LEASE OPERATOR WOODMAN-IANNITTI OIL COMPANY

ADDRESS PO BOX 308; Great Bend KS 67530

PHONE# (316) 792-2921 OPERATORS LICENSE NO. 6588

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/11/95 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? Filed w/ACO-1

Producing Formation N/A INJ. ARBUCKLE Depth to Top 3870- Bottom 3945 T.D. 3945'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	347	8-5/8"	347'	NONE
		0	3870	4-1/2"	3864'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet at each set.

Ran tubing to 3300' after circulating.

4/13/95 PLUGGED W/A total of 347 sac cement. 60/40 Pos + 8% gel. Spotted cement down tubing at bottom, 3900'; 2600'; 1700'; 700'. Cement did circulate to surface.

Job completed @ 3:00 PM 4/25/95 Filled with Redi-Mix to surface; 4 yards concrete. 1995

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 5-1-95

Address Great Bend KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOODMAN-IANNITTI OIL COMPANY

STATE OF KANSAS COUNTY OF BARTON, ss.

D. J. IANNITTI, Partner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. J. Iannitti

(Address) PO BOX 308; Great Bend KS 67530



SUBSCRIBED AND SWORN TO before me this 21st day of April, 1995

My Commission Expires: May 12, 1996

Notary Public