

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County, Sec. 11 Twp. 22S Rge. 4 (~~26~~) (W)

Location as "NE/CNW/SW" or footage from lines C SW SW NW

Lease Owner SUNRAY MID-CONTINENT OIL COMPANY

Lease Name Mitchell Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-8 19 56

Application for plugging filed 10-16 19 56

Application for plugging approved 10-16/0 19 56


Plugging commenced 10-8 19 56

Plugging completed 10-8 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Hoisington, Kansas

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 384 1/4 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|------------------|---------|---------|---------|--------|--------|------------|
| Kansas City Lime | Dry | 3435 | 3650 | 8 5/8" | 305' | none |
| Arbuckle | Dry | 379 1/4 | 384 1/4 | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1956
CONSERVATION DIVISION
WICHITA, KANSAS
10-26-56

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from TD to 240'. 240' to 150' with common cement, 1/3 sack hulls and HOWCO top plug. 150' to 40' heavy mud. 40' to surface with common cement, 1/3 sack hulls and HOWCO top plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company (Stickle Drlg Company)

Address _____

STATE OF Kansas, COUNTY OF Barton, ss.

N. E. Montgomery (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery

P. O. Box 788, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1956

My Commission Expires June 22, 1959

My commission expires _____

David White
Notary Public.

PLUGGING
FILE SEC. 11 T. 22 R. 14 W
BOOK PAGE 106 LINE 72

Sunray Mid-Continents Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
October 12, 1956

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: September 28, 1956
Drilling Completed: October 8, 1956

Mitchell #1 - NW/4 of
Section 11-22S-14W,
Stafford County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

| | |
|---------------------------|---------|
| Sand & Clay | 200 |
| Sand, Shale & Shells | 305 |
| Shale & Sand | 400 |
| Red Bed | 810 ← |
| Anhydrite | 845 |
| Shale & Shells | 1660 |
| Lime & Shale | 1860 |
| Lime | 2020 |
| Shale & Lime | 2175 |
| Lime & Shale | 2975 |
| Lime | 3124 |
| Shale & Lime | 3245 |
| Lime | 3425 |
| Shale & Lime | 3482 |
| Lime | 3564 |
| Lime & Shale | 3574 |
| Lime | 3692 |
| Lime Chert & Conglomerate | 3745 |
| Lime | 3807 |
| Arbuckle Lime | 3844 TD |

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1956
CONSERVATION DIVISION
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's Mitchell #1 - NW/4 of Section 11-22S-14W, Stafford County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING
FILE SEC. 11 T. 22 R. 14W
BOOK PAGE 106 LINE 72