

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23166-00-01
LEASE NAME Steckel Farms
WELL NUMBER # 1 'OWWO'

RECEIVED
SEP 15 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely and return to Cons. Div. office within 30 days.
1350 Ft. from South Line of Section
1815 Ft. from East Line of Section

LEASE OPERATOR L. D. Drilling, Inc. SPOT LOCATION 30' N of W/2 E/2 W/2 SE
ADDRESS 7 SW 26th Avenue Section 11 Township 22s Range 14w
CITY, STATE, ZIP Great Bend, Kansas 67530 County Stafford
PHONE # 620-793-3051 Date Well Completed 09/06/03
Character of Well D & A Date Plugging Commenced 09/06/03
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 09/06/03

The plugging proposal was approved on September 6, 2003 (date)
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? Operator to file If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 527

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Received plugging orders 09/06/03 from Richard Lacey. Cemented 7 drill collars and 7-7/8" bit (211' of iron) in hole.
Plugged with 60 sx 60/40 Poz; 6% Gel. Bottom plug @ 310' with 50sx, top plug @ 40' with 10 sx Cemented to surface. Plug down at 12:00 pm on 09/06/03. Plugged rathole with 15 sx, no mousehole. Acid Services ticket #6826. SDC reported plugging to KCC District 1 on 09/08/03.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 12th day of Sept. 15, 2003

Pamela S. Fields
(Notary Public)



My Commission Expires:

RECEIVED
SEP 15 2003
KCC WICHITA

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Steckel Farms # 1 'OWWO'

LOCATION: 30' N of W/2 E/2 W/2 SE
API: 15-185-23166-00-01

Section 11 T 22s R 14w
Stafford County, Kansas

OWNER: L. D. Drilling, Inc.

COMMENCED: 05-Sep-03

CONTRACTOR: Sterling Drilling Company, Rig #1

COMPLETED: 07-Sep-03

TOTAL DEPTH:	DRILLER	527	FEET
	LOGGER	None	FEET

Ground Elevation: 1931
KB Elevation: 1940

LOG

0 -	9 FEET	Open Hole
9 -	55 FEET	Hard Cement
55 -	200 FEET	Open Hole
200 -	400 FEET	Spotty Cement
400 -	527 FEET	Spotty Cement and Sand

CASING RECORDS

Surface Casing-8-5/8"

Existing 24#, 8-5/8" surface casing set at 361' KB on 09/19/02 by Sterling Drilling. Cemented with 350 sx 60/40 Poz, 3% Gel, 2% CC. Cement did not circulate. Tagged cement at 60' and cemented to surface using 110 sx 60/40 Poz, 3% CC.

Plugging Data of 09/29/02:

Bottom plug at 3800' with 50 sx, 2nd plug at 870' with 50 sx, 3rd plug at 390' with 50 sx, top plug at 40' with 10 sx cemented to surface.
Rathole with 15 sx, no mousehole. Job completed at 9:15 pm on 09/29/02.

Plugging Data:

Received plugging orders 09/06/03 from Richard Lacey. Cemented 7 drill collars and 7-7/8" bit (211' of iron) in hole. Plugged with 60 sx 60/40 Poz; 6% Gel. Bottom plug @ 310' with 50sx, top plug @ 40' with 10 sx Cemented to surface. Plug down at 12:00 pm on 09/06/03. Plugged rathole with 15 sx, no mousehole. Acid Services ticket #6826. SDC reported plugging to KCC District 1 on 09/08/03.