

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING FORM
K.A.R.-82-3-117

API NUMBER 15-185-22,107-0001

LEASE NAME Teichmann

WELL NUMBER B#1

990 Ft. from S Section 11

330 Ft. from E Section 11

SEC. 12 TWP. 22 RGE. 13 (KCC)

COUNTY Stafford

Date Well Completed -

Plugging Commenced 8-25-92

Plugging Completed 4:00 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Voight Oil & Gas Co. Inc.

ADDRESS Rt 3 Box 33-B, McPherson, Ks 67460

PHONE# (913) 227-3241 OPERATORS LICENSE NO. 5057

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-25-92 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filled? Yes If not, is well log attached? -

Producing Formation KC Simp Depth to Top 3398 Bottom 3640 T.D. 3725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	730	0
				5 1/2	3723	1874

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each
Bottom Plug: Ran sand to 3340 & bailed 5 sx cement.

Top Plug: Pumped 300 lb Halls, 8 sx Gel, 50 sx Cement, 7 sx Gel, 100 lbs Halls, released 8 5/8 Wiper plug, 100 sx Cement (60/40 w/6% gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Gasing Pullers, Inc. License No. 4635 CP

Address BOX 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Voigt Oil & Gas Co, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 26 day of August 1992



My Commission Expires: 4-30-96

Anna K. Burke

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1992

8-27-92 CONSERVATION DIVISION
Wichita, Kansas
Revised 05

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - TEICHMANN B-1

Located: C NE SE SE, Section 12-22S-13W, Stafford County,
Kansas

OWNER: Sterling Drilling Company, et al

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 26, 1984

COMPLETED: November 2, 1984

TOTAL DEPTH: 3725'

LOGCASING RECORD

0 - 190 Sand

190 - 733 Shale and Red Bed

733 - 1275 Shale

1275 - 3725 Lime and Shale

Ran 17 joints new 8 5/8", 23# casing.
718.17' pipe set at 730' K.B.
Cemented with 375 sacks 60/40 Pozmix, 2%
gel and 3% cc. Plug down at 8:15 AM,
10-27-84, by Howco.

Ran 109 joints used 5 1/2", 14.5#
casing. 3713.60' pipe set at 3723 K.B.
Cemented with 200 sacks 50/50 Pozmix,
18% salt, 3/4 of 1% CFR-2. 20 bbls.
salt flush ahead (400# salt). Plug
down at 3:45 AM, 10-2-84, by Howco.

Deviation Surveys: 1 1/4° at 1975'
1° at 3725'

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1992

CONSERVATION DIVISION
Wichita, Kansas