


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission,  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD  
OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

County. Sec. 13 Twp. 22N Rge. 13 (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines



Locate well correctly on above  
Section Plat

Lease Owner: Amerada Petroleum Corporation  
Lease Name: Max Tolchmann Well No. 71  
Office Address: Drawer 2040, Tulsa, Oklahoma  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date, well completed: 12/24/37 193  
Application for plugging filed: 12/24/37 193  
Application for plugging approved: 12/24/37 193  
Plugging Commenced: 12/24/37 193  
Plugging Completed: 12/24/37 193  
Reason for abandonment of well or producing formation: Dry, no oil encountered  
If a producing well is abandoned, date of last production: Did not produce 193  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. Guy Harrington  
Producing formation: Arbuskie lime Depth to top: 3792' Bottom: 4015' Total Depth of Well: 4015' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuskie lime	Dry	3792'	4015'	10-5/8"	260' 7"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

pumped in 10.67 rotary mud, filling hole to within 275', placed Halliburton wood plug and dumped one half yard on top of plug and and dumped 15 sacks of cement on top of crushed rock, filled hole to within 45' of top with rotary mud, and place Halliburton wood plug and dumped 10 sacks of cement on plug and welded top of surface pipe closed.

Recd 12-27-37

PLUGGING  
FILE NO. 12-22-130  
BOOK PAGE 1 LINE 43

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to: Amerada Petroleum Corporation  
Address: Drawer 2040, Tulsa, Oklahoma

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. J. Lusk*  
Box 207, Tonaw, Okla.  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January, 1938

My commission expires May 7, 1938

*Yveta Powell*  
Notary Public.