

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 12 Twp. 22 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Lee Phillips Oil Company
Lease Name Curtis Well No. 1
Office Address 1407 Union National Buildig Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 15 1961
Application for plugging filed December 15 1961
Application for plugging approved December 15 (verbally) 1961
Plugging commenced December 15 1961
Plugging completed December 15 1961
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	264'	8 5/8"	264'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 240' with plug and 20 sacks of cement at this point. Heavy mud to 35' with plug and 10 sacks of cement at this point.

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1962 1-4-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company
Address P.O. Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
ALLAN HARMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
P.O. Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of January, 1962
Mary E. Van Pelt
Notary Public.

My commission expires 1-20-62



D R I L L E R S L O G

Company: Lee Phillips Oil Company
 Farm: Curtis # 1
 Commenced: December 7, 1961

SE NW NW Section 12-22-13W
 Stafford County, Kansas
 Completed: December 15, 1961

Elevation: 1881 KB

0 - 220 sand
 220 - 264 shale
 264 - 720 red bed & shale
 720 - 746 Anhydrite
 746 - 1500 shale & shells
 1500 - 1800 shale & lime
 1800 - 2200 lime & shale
 2200 - 2880 shale & lime
 2880 - 3105 lime & shale
 3105 - 3197 lime
 3197 - 3201 Heebner
 3201 - 3226 lime
 3226 - 3330 shale
 3330 - 3365 lime
 3365 - 3435 lime & shale
 3435 - 3600 lime
 3600 - 3690 Viola
 3690 - 3705 Simpson
 3705 Total depth

RECEIVED
 STATE OF KANSAS

JAN 4 1962

CONSERVATION DIVISION
 Wichita, Kansas

Set 264 feet of 8 5/8 inch surface pipe. Cemented with 300 sacks of common cement with 2% calcium chloride.

Tops: Anhydrite - 720
 Heebner - 3197
 Brown Lime - 3329
 Lansing - K.C. - 3346
 Conglomerate - 3597
 Viola - 3605
 Simpson - 3694

Dry, plugged
 and abandoned.

A F F I D A V I T

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms
 Allan Harms

Subscribed and sworn to before me this 2 day of January, 1962.

Mary E. Van Pelt
 Notary Public

My commission expires 1-20-62