

15-185-19380-0008

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bittling Building
Wichita, Kansas

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 28 Twp. 23S. Rge. (E) 12 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE NW 1/2
Lease Owner Shell Oil Co., Inc.
Lease Name F. Heyen "B" Well No. 1
Office Address Box 744, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 31 19 41
Application for plugging filed May 8 19 46
Application for plugging approved May 13 19 46
Plugging commenced June 13 19 46
Plugging completed June 17 19 46
Reason for abandonment of well or producing formation Oil Depleted

If a producing well is abandoned, date of last production October 7 19 45
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation Arbuckle Depth to top 3844 Bottom Total Depth of Well 3847 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	2240' oil 3/4 hours. Ind. Cap. 8237 oil & O water	3845	3847	8 5/8" 4 1/2"	312' 3845'	None 1650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Dumped 4 sax cement on bottom. Mudded hole to 260'; set 10' rock bridge; and dumped 15 sax cement to 250'. Filled surface pipe with mud & capped with 10 sax cement into base of cellar.

FILE BOOK 28-23-12W 54-1121-2

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Shell Oil Co., Inc.
Address c/o W. M. Gholson, Box 744, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. M. Gholson (employee of owner) or town or operator

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *W. M. Gholson*

Box 744, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1946

Betty Postlethwaite
Notary Public.

My commission expires January 24, 1949

7-18-46

15-185-19380-0000

SHELL, F. HEYEN "B" #1
SE SE NW Section 28-23S-12W
Bedford Pool
Stafford County, Kansas

CASING RECORD

8 5/8" Cem 312 with 125 sax
4 1/2" Cem 3845 with 100 sax

- 0 - 50 Dirt & clay
- 140 Sand
- 190 Clay
- 669 Red rock
- 695 Anhydrite & shale
- 1070 Salt & shale
- 1307 Shale & shells
- 1519 Salt & anhydrite
- 1670 Shale & shells
- 1710 Lime & anhydrite
- 1745 Shale & shells
- 1838 Lime & anhydrite
- 1863 Lime
- 1920 Sand & anhydrite
- 1966 Lime
- 2066 Shale & broken lime
- 2087 Lime
- 2680 Shale
- 2785 Shale & lime
- 2944 Shale
- 3000 Lime
- 3022 Shale & shells
- 3055 Lime
- 3119 Lime & chert
- 3313 Lime
- 3385 Lime & shale
- 3692 Lime
- 3715 Conglomerate
Top Sooy Conglomerate 3692
- 3775 Chert & cherty lime
- 3812 Shale
Top Viola 3715
- 3826 Sand & dolomite
Top Simpson Shale 3775
- 3843 Shale
Top Simpson Sand 3812
Top Brecciated Dolomite 3843
Top Arbuckle 3844
- 3847 Dolomite TD

PLUGGING
 FILE NO. 28 23 12W
 BOOK PAGE 54 LINE 10





STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 800 BITTING BUILDING
 WICHITA, KANSAS

15-185-9380-0000

July 13, 1946

IN REPLY PLEASE
 REFER TO THIS
 SUBJECT

Shell Oil Company, Inc.

Box 744

Great Bend, Kansas

IN ACCOUNT WITH Conservation Division, State Corporation Commission
 Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ 25.00

pd 7/18/46

Well No. 1
 Farm Hoyer "B"
 Description SE SW NW 22-22-12N
 County Stafford
 File: 54-10

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due July 13, 194 6

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a plugging record covering this well, to complete this file.