

15-185-1937A-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Stafford County. Sec. 28 Twp. 23 Rge. 11/6/12 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C. NW. SE. NW
Lease Owner. Harry Gore
Lease Name. Heyen Well No. 1
Office Address. 400 Brown Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19.
Application for plugging filed 5-31-46 19.
Application for plugging approved 5-31-46 19.
Plugging commenced 5-31-46 19.
Plugging completed 5-31-46 19.
Reason for abandonment of well or producing formation Depleted

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. Depth to top. Bottom. Total Depth of Well. 3852 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was cemented 3852' to 3812'.
5 sacks cement, heavy mud 3812' to
250' bridge cement 250' to 200', 15
sacks. Mud 200' to 15' cement into base
of cellar, 10 sacks. 311' of 8 5/8
cemented and left in hole.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harry Gore
Address. Brown Bldg.
Wichita, Ks.

STATE OF Kansas COUNTY OF Sedgewick, ss.
I, Ralph Gore, Partner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Gore

(Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 1948

Lucille Harv

Notary Public.

My commission expires Oct 21, 1950

PLUGGING
FILE SEC 78 T 73 R 17W
BOOK PAGE 56 LINE 18


15-185-19379-0000

HARRY GORE(SHELL OIL CO., INC.)
 Floyd Heyen "B" No. 1.

SEC. 28 T. 23 R. 12 W
 NW SE NW
 990' f SL 990' f EL NW $\frac{1}{4}$

Total Depth. 3852'
 Comm. 12-4-41 Comp. 1-20-42
 Shot or Treated.
 Contractor. Mercury Drlg. Co.
 Issued. 2-7-42

County. Stafford



CASING:
 8 5/8" 311' Cem.
 5 1/2" 3841' Cem.

Elevation.

Production. Pot. 203 B.

Figures Indicate Bottom of Formations.

166 BW, Pmp

sand	100
sand & clay	200
red rock	300
lime shells	322
red rock	683
anhydrite	705
shale & shells	981
shale & lime shells	1160
salt & shale	1440
shale & lime	1705
shale & lime shells	1797
lime brkn	1911
lime	2051
shale & lime shells	2161
lime	2270
shale & lime	2435
sand & lime	2450
lime brkn	2564
shale & lime	2995
lime	3279
shale	3340
shale & lime	3456
lime brkn	3518
shale & lime	3610
lime brkn	3703
lime & shale	3725
chert	3748
chert & lime	3772
shale	3840
lime	3842
dolomite	3852
Total Depth.	

Top Arbuckle dolomite 3842

Acidized 500 Gals. 1-15-42

No show oil or water after drilling cement plug
 and cleaning out 3242.

1300' of oil and 3 BW at bottom after 20 hrs.

1-1-42 2400' of fluid 47 $\frac{1}{2}$ hours bail 2 $\frac{1}{2}$ BW

13 1348

PLUGGING
 FILE SEC 78 T. 23 R. 12 W
 BOOK PAGE 56 LINE 18