


15-185-12107-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 28 Twp. 23 Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NW SW SE
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Knoche Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/2 19 56
Application for plugging filed 9/4 19 56
Application for plugging approved 9/5 19 56
Plugging commenced 9/8 19 56
Plugging completed 9/13 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation Depth to top Bottom Total Depth of Well 3862 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None
				5 1/2"	3859'	1898'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 3848'. Dumped 5 sax cement w/dump bailer; top of cement 3815'. Filled hole with mud to 240', set rock bridge, dumped 20 sax cement. Top of cement, 180'. Filled hole with mud to 35' set rock bridge, dumped 10 sax cement for cap.

9-18-56

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 56

My commission expires 6/17/58 Notary Public.

PLUGGING
FILE SEC 28 T. 23 R. 12W
BOOK PAGE 96 LINE 36

15-185-12107-0000

Bennett & Roberts Drilling Co.
Knoche #1

NW SW SE 28-23-12W
Stafford Co., Kans.

Contractor: Bennett & Roberts Drilling, Inc.

R.T.D. 3862

Commenced 8/14/56
Completed 8/25/56

Casing Record
8 5/8" Set @ 247' w/175 sx cmt.
5 1/2" Set @ 3859' w/75 sx cmt.

----- Figures Indicate Bottom of Formation -----

Sandy Clay & Surface Soil	40
Sand	55
Sandy Shale	70
Sand	145
Sand, Shale & Shells	215
Red Bed	690
Anhydrite	715
Shale & Shells	1210
Shale & Lime Streaks	1475
Shale & Lime	2050
Lime	2165
Shale & Lime	3201
Shale & Lime Streaks	3298
Shale & Lime	3385
Lime	3700
Shale & Lime Streaks (Cong)	3709
Shale & Lime	3760
Chert & Lime	3797
Lime & Shale	3824
Sand	3846
Lime & Shale	3862

STATE OF KANSAS)
RUSSELL COUNTY)

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By *Ann Lake*

Subscribed and sworn to before me this 28th day of August, 1956,

Clara Hummel
Notary Public

My Commission Expires 6/17/58

RIP
STATE
SE
CONSERVATION
Wichita

PLUGGING
FILE SEC 28 T 23 R 12W
BOOK PAGE 96 LINE 36