

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15485-22093-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 23S RGE. 12 E/W
 Location as in quarters or footage from lines:
S/2 NE/4

Lease Owner West Trail Exploration Co.
 Lease Name Rice Well No. 1
 Office Address 1531 Stout St., Suite 530, Denver, CO 80202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 10-9-84
 Application for plugging filed 10-9-84
 Plugging commenced 10-9-84
 Plugging completed 10-9-84
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3907 KB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. D & A, Plugged as follows:

Filled hole w/mud, pumped 50 sx 60/40 pozmix, 2% gel, 3% cc, thru open end drill pipe
@ 690', mud to 340', pumped 50 sx thru open end drill pipe, mud to 40', 1/2 sk hulls &
wood plug for solid bridge, pumped 10 sx to base of cellar, circulated 15 sx in rathole,
10 sx in mousehole. Completed @ 2:15 AM, 10-9-84 by "SUN".

RECEIVED
 STATE CORPORATION COMMISSION


OCT 22 1984

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Cougar Drilling Co., Inc. 10-22-84
555 N. Woodlawn, Suite 114, Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.
John S. Crowe (employee of owner) or ~~(owner)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) John S. Crowe
555 N. Woodlawn, #114, Wichita, KS
 (Address) 67208



SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 84
Phyllis A. Freeman
 Notary Public.
 My Commission expires: 6-9-86