

15-185-21254-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 23S RGE. 12W E/W
Location as in quarters or footage from lines:
100' S of SE SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Petroleum Energy, Inc.
Lease Name Rice #1 Well No. _____
Office Address Suite 710, One Twenty Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/29/81
Plugging completed 6/2/81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 3858'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	286'	None
				4 1/2"	3850'	3048'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in. Pushed plug to 3560'. Sanded to 3500' and set 4 sacks cement. Pulled 23"
stretch. Shot casing at 3066' and pulled a total of 77 joints. Plugged well with
25 sacks gel, 8 sacks hulls and 125 sacks 50/50 pos 4% gel 3% cc. 900# shut in pressure.
Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 4 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING CONSERVATION DIVISION
Wichita, Kansas.

6-4-81

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 81

My Commission expires: _____



Joan Kelso
Notary Public.

DRILLERS LOG

15485-21254-0000

OPERATOR: Petroleum Energy, Inc. 710 One Twenty Bldg. Wichita, Ks. 67202
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Rice Well No. #1
Sec. 29 T. 23S R. 12W Spot 100' S of SE SE NE
County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 286' with 250 Sxs. 3% cc
Production: 3850' @ 0 1/2" with 150 Sxs. 2% gel

Type Well: Oil Total Depth 3858'

Drilling Commenced: 3-21-81 Drilling Completed 4-1-81

Formation	From	To	Tops
Cellar	0	7	
Shale, Lime	7	955	
Shale	955	2077	
Shale, Lime	2077	2281	
Shale	2281	2417	
Shale, Lime	2417	2595	
Shale	2595	2995	
Shale, Lime	2995	3276	
Shale	3276	3410	
Lime	3410	3858	

-LB- 1872

Directions - 281 south out of Great Bend to 1st St. Road. TURN EAST - (5) miles then south 2 1/2 miles, west into location.

COMPLETION RECORD

Liner Record: Size _____ From _____
Cementing Record: _____ Sacks _____
Perforating Record: _____

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1981

CONSERVATION DIVISION
Wichita, Kansas

Formation	Perforated Interval

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

