

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-10114-00-01

LEASE NAME Rice

WELL NUMBER SWD

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR RAMA Operating Co., Inc.

SEC. 29 TWP. 23 RGE. 12W(E) or (W)

ADDRESS P. O. Box 159 Stafford, KS 67578

COUNTY Stafford

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 3911

Date Well Completed

Character of Well SWD

Plugging Commenced 12-24-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-27-96

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4180'

Show depth and thickness of all water, oil and gas formations.

1-10-97

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	674'	none
				4 1/2	3970'	2518'

Describe in detail the manner in which the well was plugged, indicating where the mud/fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s' Sanded bottom to 3350' & ran 4 sks cement. Shot at 2518', pipe came free. Pulled casing up to 710'; circulated hole w/35 bls fresh H2O. Pumped 250# hulls then 50 sks cement & 50# hulls. Displaced to 710'. Pulled rest of casing out of hole. Circulated cement from 120' to surface with 30 sks cement. Hole stayed full. 60/40 poz 6% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P. O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t: the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 96

James Herzberg
 Notary Public

My Commission Expires:

