

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20084-00-00

LEASE NAME SIEFKES "B" 1C

WELL NUMBER #12

1650 Ft. from Section L

1650 Ft. from Section L

SEC. 3 TWP. 22 RGE. 12 (E) W. 1/4

COUNTY STAFFORD

Date Well Completed 2-73

Plugging Commenced 8-06-00

Plugging Completed 8-06-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR L. D. DRILLING, INC.

ADDRESS R.R. 1 BOX 183 B GREAT BEND, KANSAS 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 16, 2000 (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Arbuckle Depth to Top \_\_\_\_\_ Bottom T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	654	8"	656'	none
production		0	3679	5 1/2"	3679'	none

Describe in detail the manner in which the well was plugged, indicating where the mud flu placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each

Hooked to 5 1/2" csg. Mixed 200# hulls, 25 sx 65/35 6% gel w/100% hulls, 26 sx Gel Spacer (65 bbls) 50 sx, 65/35 6% gel Max pressure 1300# shut in =400  
Hooked to annulus and mixed 125 sks 65/35 6% Gel Max pressure = 400# shut in=200#  
Total 200 sx. 65/35 6% Gel 26 gel 300# hulls

Name of Plugging Contractor Allied Cementing Lic. RECEIVED KANSAS CORPORATION COMMISSION

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc. DEC 22 2000

STATE OF Kansas COUNTY OF Barton CONSERVATION DIVISION WICHITA, KS

Bessie DeWerff (Employee of Operator) or (Owner)

above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Bessie DeWerff  
Bessie DeWerff

(Address) R.R. 1 Box 183 B Great Bend Kansas 67530

SUBSCRIBED AND SWORN TO before me this 21st day of December 2000

Rashell Patten  
Notary Public  
Rashell Patten

My Commission Expires: 2-02-03

