

STATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-21,059-00-00

LEASE NAME Siefkes "B"

WELL NUMBER 13

330 Ft. from N Section Line

1320 Ft. from E Section Line

SEC. 3 TWP. 22 RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 12-17-01

Plugging Completed 12-19-01

RECEIVED
DEC 3 2001
WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS P.O. Box 183B Great Bend, Kansas 67530

PHONE (620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	652	None
				5-1/2"	3698	2214'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3380' and 5 sx. cement. Shot pipe @2400' and 2214', pulled casing up to 680', pumped 21 sx. gel, 300# hulls to circulate and 50 sx. cement. Pulled casing up to 300', pumped 40 sx. cement, pulled up to 40' and topped off with 10 sx. cement. Plugging Complete. 60/40 pos, 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of December 2001

[Signature]
Notary Public

My Commission Expires:

