


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 12 Twp. 16S Rge. (E) 15(W)  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C SW SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name BEN KARST Well No. 2  
Office Address Box 797 - Gt. Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5/8 1966  
Application for plugging filed 5/8 1966  
Application for plugging approved 5/8 1966  
Plugging commenced 5/8 1966  
Plugging completed 5/8 1966  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan - Russell, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3348 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	359'	8-5/8"	359'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1/4 sack hulls & wooden plug set @ 350'  
Mixed 25 sacks cement through drill pipe  
1/2 sack hulls & wooden plug set @ 40'  
Mixed 10 sacks cement through drill pipe

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 11 1966  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Box 797 - Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 797 - Gt. Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 66

My commission expires Jan. 26, 1967

[Signature]  
Carmen R. Cook, Notary Public.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 11 1966  
 CONSERVATION DIVISION  
 W-15W, Kansas

WELL LOG

Chief Drilling Co., Inc.  
 Box 797  
 Great Bend, Kansas

BEN KARST #2  
 C SW SW Sec. 12-16S-15W,  
 Barton County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 5-2-66  
 Completed: 5-8-66

Casing Record: 8-5/8" @ 359' w/200 sacks 60-40 Pozmix

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale with Lime & Sand	0	360	1936 Gr.
Shale & Lime Stringers	360	490	1938 D.F.
Sand & Shale	490	580	1941 K.B.
Red Bed & Sand	580	715	
Red Bed	715	955	
Anhydrite	955	984	
Shale & Lime	984	1980	
Lime	1980	2295	
Shale & Lime	2295	2883	
Lime	2883	3109	
Shale & Lime	3109	3128	
Lime	3128	3348	
Total Depth	3348		

<u>FORMATION TOPS</u>	
Anhydrite	955 + 986
Topeka	2883 - 942
Heebner	3109 - 1168
Toronto	3128 - 1187
Lansing	3175 - 1234
Total Depth	3348 - 1407

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW SW Sec. 12-16S-15W, Barton County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
 V. Richard Hoover, President

Subscribed and sworn to before me this 10th day of May, 1966.

*Carmen R. Cook*  
 Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.