

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.009-23250-0000

API NUMBER 15-009-23,250

LEASE NAME Oscar Karst

WELL NUMBER #1

SPOT LOCATION SE NW NE

SEC. 12 TWP. 16 RGE. 15 (E) of (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-27-86

Plugging Completed 7-3-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Woodman & Lannitti Oil Company

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE # (316) 792-1934 OPERATORS LICENSE NO. 6588

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	940'	None
				5-1/2"	3475'	2,728.76'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3100' and 5 sacks cement. Shot casing at 2700'. Pulled 63 joints of 5-1/2" casing. B.J. Titan squeezed well with 5 sacks hulls and 125 sacks thrifty mix cement at 800 psi maximum pressure and 650 psi shut in.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

JUL 15 1986

CONSERVATION DIVISION  
Wichita, Kansas  
SUBSCRIBED AND SWORN TO before me this 14th day of July, 1986

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman  
Notary Public