

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-185-21,850-0000

LEASE NAME STARGEL

WELL NUMBER #3

SPOT LOCATION NE SW NE

SEC. 4 TWP. 22 RGE. 12 (E) OR (W)

COUNTY Stafford

DATE WELL COMPLETED 9-21-83

PLUGGING COMMENCED 9-21-83

PLUGGING COMPLETED 9-21-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR BROUGHTER OIL, INC

ADDRESS P.O. Drawer 1367
Great Bend, Ks 67530

PHONE #(316) 793-5610 OPERATORS LICENSE NO. 6393

CHARACTER OF WELL D/A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dist. #1 Dodge City, Ks

IS ACC-1 FILED? No IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3730'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	311'	0

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. PTA w/140 sacks of 60/40 poz. 2% Gel. 3% CC First Plug @3600' with 25 sks; Second Plug @450' with 50 sks; Third Plug @300' with 40 sks. Top Plug 40' with 10 sks: Rat Hole 15 sks.: Mouse Hole 5 sks.

PLUGGING COMPLETE

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)


NAME OF PLUGGING CONTRACTOR HALLIBURTON SERVICES LICENSE NO. 5287
ADDRESS 2400 Main, Great Bend, Ks 67530

STATE OF Kansas COUNTY OF Barton, SS.

Joe E. Brougher (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Joe E. Brougher
Joe E. Brougher
(ADDRESS) P.O. Drawer 1367
Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 4th DAY OF October, 1983



Pamela R. Stegman
NOTARY PUBLIC
Pamela R. Stegman

MY COMMISSION EXPIRES: 7-11-87
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1983

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

DRILLERS' WELL LOG

BROUGHER OIL, INC.

STARGEL #3

NE SW NE Sec. 4-22-12
Stafford County, Kansas

DATE COMMENCED: 9-15-83

DATE COMPLETED: 9-21-83

ELEVATION: 1867 DF; 1859 GL

Surface Pipe: 8 5/8" Casing set @311',
cemented w/250 sacks 60/40 pozmix,
2% gel, 3% CC. Cement did circulate.

- 0 - 215' Sand
- 215 - 315' Red Bed
- 315 - 829' Shale
- 829 - 1465' Shale
- 1465 - 1620' Shale & Lime
- 1620 - 2080' Shale & Lime
- 2080 - 2390' Shale & Lime
- 2390 - 2810' Lime & Shale
- 2810 - 3175' Lime & Shale
- 3175 - 3386' Lime
- 3386 - 3545' Lime
- 3545 - 3676' Lime
- 3676 - 3686' Arbuckle
- 3686 - 3696' Arbuckle
- 3696 - 3711' Arbuckle
- 3711 - 3730' Arbuckle
- 3730' RTD
- D/A

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{ss.}

Terry Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Terry L. Williamson

Terry Williamson

Subscribed and Sworn to before me this 30th day of September, 1983.

My Commission Expires:

7-11-87


Pamela R. Stegman

Notary Public
Pamela R. Stegman

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1983

CONSERVATION DIVISION
Wichita, Kansas



RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1983

CONSERVATION DIVISION
Wichita, Kansas